6. The Contractor should not interfere in any way with the traffic or legitimate movement of the public in the premises.

7. Grazing is allowed only between 10 A.M. and 5 P.M.

8. The following portions of the Farm are closed for grazing :—

(*a*) The cultivated areas in the Farm to the north of the main drain.

(*b*) The central main drain and the bunds on either side of it.

9. No compensation shall be paid for any portion of the grazing area if required by Government for improvements, etc.

10. The right of grazing of the departmental bullocks within the leased area is reserved.

11. The Contractor should make proper arrangements for watching the cattle and prevent their doing damage to Farm crops, fences, buildings, etc.

12. The Contractor should compensate for any loss or damage committed to the crops, etc., or any other Government property located within the Farm premises during his lease either by himself or by his agents.

13. The Contractor should not remove the cattle manure from the grazing area.

14. The name of the successful tenderer will be notified and he will be required to pay up the whole amount due before the end of the month.

15. The final acceptance of the tender will rest with the Superintendent, Government Gardens in Mysore, who does not bind himself to accept the highest or lowest tender or assign any reason whatever for the rejection of any tender.

16. On acceptance of one of the tenders, the deposit money on the rejected tenders will be returned on the 15th instant.

17. After confirmation of the tender, the successful tenderer will be required to execute the usual agreement on a stamped paper specifying all the conditins with a deposit of Rs. 50 as earnest money to be taken in case any damages which may be done to the Farm crops, etc., or the Farm, in default of which his tender will be considered as cancelled and his deposit money forfeited to Government and the lease will be resold at his risk.

18. In case of complaints preferred by the purchaser, the decision of the Superintendent Government Gardens in Mysore is final.

H. C. JAVARAYA,
Superintendent.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification dated 29th July 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M., on the 19th August 1932, for extension to the Office of the Superintendent, Power and Lighting, Bangalore.

1. The tenders will be opened in public at 2 P.M., on the 19th August 1932. The works should be completed within three months and the monthly progress should not be less than Rs. 1,200.

2. The quantities given are approximate, and the plans, detailed estimates and conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or in Government promissory notes, as earnest money and be superscribed "Tenders for constructing extensions to the Office of the Superintendent, Power and Lighting, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tender, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of the Notification of the acceptance.

10. Water for construction should be got at the Contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

12. The Contractor should be bound by conditions of schedule contract of the Electrical Department.

Statement of Quantities for constructing extensions to the Office of the Superintendent, B. P. L.

Sl. No.	Items of Work	Unit	Quantity
1a	Earth work excavation and filling in basement ...	C. yd.	44
b	Earth work filling in basement (earth brought from outside).	,,	13
2a	Stone jelly concrete foundation ..	C. ft.	396
b	Coursed rubble stone in mortar foundation and basement ...	,,	1,116
c	Do in mortar courses to tally with the existing work.	,,	1,139
d	Stone slabs 6″ thick exposed part one line dressed and set in mortar.	S. ft.	152
e	Cut stone arch work ...	C. ft.	17
f	Quoin stones 1″ chisel drafted in superstructure ...	,,	36
g	Wire cut brick in mortar ..	,,	90
h	Chunam plastering stone work ...	Sqr.	12·76
i	Calcarium distemper washing 2 coats ..	,,	12·76
j	Dado work as per existing work ...	R. ft.	41
k	Chunam pointing with thread lines complete ...	Sqr.	14·83
l	Whitewashing 2 coats ..	,,	3·40
3a	Flooring with 1st Class Mangalore tile on 3″ concrete and cement pointed.	,,	3·86
b	Cuddapah slab (1½″ thick) flooring on 3″ concrete and cement pointed.	,,	5·28
4a	Roofing with 1st Class Mangalore tiles with ceiling tiles on teakwood reepers 2″ x 1″.	,,	6·27
b	Roofing with single 1st class Mangalore tiles on teak wood reepers 2″ x 1″.	,,	8·09
c	Ridge tiles set in mortar and cement pointed ...	R. ft.	17
5a	Teakwood wrought and put up with 2 coats of wood oiling complete.	C. ft.	72·48
b	Teakwood panelled door 1½″ thick shutters with fixtures complete as per existing work.	S. ft.	32
c	Teakwood glazed windows 1¼″ shutter with iron bars, etc., complete as per existing work.	,,	113
d	Teakwood ventilators glazed fixed complete ...	,,	32
e	Teakwood circular ventilators glazed fixed complete ...	,,	13
f	Teakwood ornamental eve board as per existing work (12″ x ¾″).	R. ft.	102
g	Teakwood planking 1″ thick for valleys fixed complete ..	S. ft.	28
h	Plain Galvanised iron sheeting for valley fixed complete as per existing work.	,,	28
i	Silicate painting 3 coats ...	Sqr.	12·26
6	Removing and refixing an old window 5′ x 7½′ into the new masonry.		1 Item
7	Steel truss 25 feet clear span fixed complete as per existing work.	each	1
8	Removing and refixing Mangalore tile roofing with reepers, eve boards, finials, etc., on the gable wall including end rafters.		1 Item
9	Removing and refixing Mangalore tile roofing with reepers and eve board, etc. of the verandah roof.		1 Item
10	Constructing valley complete ...		1 Item
11	Cement border 3″ x 3″ with Galvanised iron reinforcement at junction of wall and verandah roof.	R. ft.	77
12	Chunam patty 6″ x 3″ at ends of main roof ...	,,	38
13	Dismantling the existing pillar and rebuilding the same in the new position using new bricks if necessary and chunam pointed, etc., complete.		1 Item
14	Dismantling the existing drain and reconstructing the same using old slabs with chunam concrete and cement plaster.	,,	78
15	Constructing new drain with Cuddapah slab chunam concrete and cement plaster as per existing.	,,	36
16	Putting chunam concrete 3″ thick between wall and drain and cement plaster 1/2″ thick.	,,	114
17	Dismantling steps and removing debris ...		1 Item
18	Inserting Bound stones 2′ x 1½′ by 1/2′ for joining old and new masonry both in foundation and superstructure.	S. ft.	96
19	Making holes in old wall to insert rafters ...	each	20
20	Repairs to walls and flooring etc., of old work after the extension is built.		1 Item